



The CNGS

Operation and Perspectives

Edda Gschwendtner, CERN




Outline

- Introduction
- CNGS Facility
- Performance and Operational Challenges
- Perspectives
- Summary

Beam Facilities at CERN

2010




SDM 11.05.2005 - dimensions not proportional to machines real sizes / from AB_complex.cdr

Neutrino Introduction

→ **CNGS (CERN Neutrinos to Gran Sasso):**
 long base-line **appearance experiment:**

- Produce muon neutrino beam at CERN
- **Measure tau neutrinos in Gran Sasso, Italy (732km)**



$\sim 4 \cdot 10^{19}$ p/year

$\sim 2 \cdot 10^{19}$ ν_{μ} /year

~ 2 ν_{τ} /year ($\sim 1 \cdot 10^{17}$ ν_{μ} /year)



Approved for **$22.5 \cdot 10^{19}$ protons on target** i.e. 5 years with $4.5 \cdot 10^{19}$ pot/yr
 (200 days/yr, intensity of $2.4 \cdot 10^{13}$ pot/extraction) → **Expect ~ 10 ν_{τ} events in OPERA**

Physics started in 2008 → today: **$12.7 \cdot 10^{19}$ pot**

Neutrino Detectors in Gran Sasso

OPERA

1.2 kton emulsion target detector
 ~146000 lead emulsion bricks







Veto BMS: Brick Manipulating System Spectrometer: RPC, Drift Tubes, magnet Target Tracker

→ A. Ereditato, Tue, 10:15

ICARUS

600 ton Liquid Argon TPC



→ F. Pietropaolo, We, 9:50

CNGS: Conventional method to produce neutrino beam

→ Produce high energy pions and kaons to make neutrinos



CNGS Beam at CERN

Lake Geneva

LHC



CNGS

SPS

PS

CERN


- From SPS: 400 GeV/c
- Cycle length: 6 s
- 2 Extractions: separated by 50ms
- Pulse length: 10.5 μ s
- Beam intensity: $2 \times 2.4 \cdot 10^{13}$ ppp
- Beam power: up to 500kW
- $\sigma \sim 0.5$ mm



CERN NEUTRINOS TO GRAN SASSO

Underground structures at CERN

- █ Excavated
- █ Concreted
- █ Decay tube (2nd contract)



CNGS Primary Beam Line

100m extraction together with LHC, 620m long arc to bend towards Gran Sasso, 120m long focusing section

Magnet System:


- 73 MBG Dipoles
 - 1.7 T nominal field at 400 GeV/c
- 20 Quadrupole Magnets
 - Nominal gradient 40 T/m
- 12 Corrector Magnets

Beam Instrumentation:

- 23 Beam Position Monitors (Button Electrode BPMs)
 - recuperated from LEP
 - Last one is strip-line coupler pick-up operated in air
 - mechanically coupled to target
- 8 Beam profile monitors
 - Optical transition radiation monitors: 75 μm carbon or 12 μm titanium screens
- 2 Beam current transformers
- 18 Beam Loss monitors
 - SPS type N_2 filled ionization chambers






CNGS Secondary Beam Line




1 Target unit: 13 graphite rods 10cm
 1 Magazine: 1 unit used, 4 in situ spares

Muon detectors:
 2x41 LHC type BLMs




CNGS Timeline until Today








CNGS Physics Run: Comparison of Yearly Integrated Intensity



Different CNGS Duty Cycles (2011)



<77%> duty cycle for CNGS with LHC Operation

<57%> duty cycle for CNGS with LHC Operation and Fixed Target program

→ Geodesic alignment

<u>Examples:</u>	<u>effect on V_{τ} cc event</u>
horn off axis by 6mm	< 3%
reflector off axis by 30mm	< 3%
proton beam on target off axis by 1mm	< 3%
CNGS facility misaligned by 0.5mrad (beam 360m off)	< 3%

High intensity, high energy proton beam with short beam pulses and small beam spot


- Thermomechanical shocks by energy deposition (target, windows, etc...)
- Induced radioactivity
- Remote handling and replacement of equipment

→ Good tuning and interlock system



→ Monitoring of beam and equipment

Beam Position on Target


Beam trajectory tolerance on target must be below 0.5mm




- Excellent position stability; ~ 50 (80) μm horiz (vert) over entire run.
- No active position feedback is necessary
 - 1-2 small steerings/week only





Horizontal and vertical beam position on the last Beam Position Monitor in front of the target



Muon detector




Intensity on Ionization Chambers vs BPM



CERN NEUTRINOS TO GRAN SASSO


Underground structures at CERN

- Excavated
- Concreted
- Decay tube (2nd contract)



Muon Monitors: Online Feedback

Very sensitive to any beam changes! → Online feedback on quality of neutrino





– Offset of target vs horn at 0.1mm level

- Target table motorized
- Horn and reflector tables not

➡ Muon Profiles Pit 1

– Offset of beam vs target at 0.05mm level


➡ Muon Profiles Pit 2



$$\text{Centroid} = \frac{\sum(Q_i * d_i)}{\sum(Q_i)}$$

Q_i is the number of charges/pot in the i -th detector,
 d_i is the position of the i -th detector.

CNGS Radiation Issues I



No surface building above CNGS target area
 → large fraction of electronics in tunnel area

Failure in ventilation system installed in the CNGS Service gallery


→ due to radiation effects in electronics (**SEU**- Single Event Upsets- from high energy hadrons)

Modifications during shutdown 07/08:

- Move most of the **electronics out** of CNGS tunnel area
- **Create radiation safe area** for electronics which needs to stay in CNGS
- **Add shielding** → 53m³ concrete → up to 6m³ thick shielding walls


→ triggered a huge radiation to electronics campaign at LHC!!!

CNGS Radiation Issues II



Temperature probes reacted immediately on failure of the ventilation system

- Alarm in CERN Control Centre
- Switch off beam




CNGS Radiation Issues III

Sump and Ventilation System

After 1st year of high intensity CNGS physics run: Modification needed for

- Sump system in the CNGS area
 - **avoid contamination** of the drain water by tritium produced in the target chamber
 - Try to remove drain water before reaches the target areas and gets in contact with the air
 - Construction of two new sumps and piping work
- **Ventilation system configuration and operation**
 - Keep target chamber under under-pressure with respect to all other areas
 - Do not propagate the tritiated air into other areas and being in contact with the drain water



→ **Radiation monitors**



CNGS – Perspectives

Approved for $22.5 \cdot 10^{19}$ protons on target


i.e. 5 years with $4.5 \cdot 10^{19}$ pot/ year \rightarrow Expect ~ 10 ν_{τ} events in OPERA

2011, 2012: $4.7E19$ pot
 2013: 0 pot
 2014: $2.3E19$ pot
 2015: $4.7E19$ pot

} LS1

\rightarrow Physics program would finish in 2015

\rightarrow By end 2012 we would have reached $\sim 19E19$ pot



CNGS Facility: Intensity Limitations

→ Design of secondary beam line elements, RP calculations

→ (Horn designed for $2E7$ pulses, today we have $1.5E7$ pulses → spare horn)

→ Intensity upgrade from the injectors are being now evaluated within the LHC Injector Upgrade Project (LIU)

Intensity per PS batch	# PS batches	Int. per SPS cycle	200 days, 100% efficiency, no sharing	200 days, 55% efficiency, no sharing	200 days, 55% efficiency, 60% CNGS sharing
		<i>[prot./6s cycle]</i>	<i>[pot/year]</i>	<i>[pot/year]</i>	<i>[pot/year]</i>
2.4×10^{13} - Nominal CNGS	2	4.8×10^{13}	1.38×10^{20}	7.6×10^{19}	4.56×10^{19}
3.5×10^{13} - Ultimate CNGS	2	7.0×10^{13}	(2.02×10^{20})	(1.11×10^{20})	(6.65×10^{19})

Design limit for target, horn, kicker, instrumentation

Design limit for horn, shielding, decay tube, hadron stop

Working hypothesis for RP calculations

CNGS working hypothesis

- Beam performance since start of physics run in 2008 CNGS is very good
 - Today we have already delivered more than half of the approved total protons on target.
 - Looking forward to seeing more tau-neutrinos
- CNGS program beyond 2013 not yet approved
 - Statement from OPERA in summer 2012
- Operating and maintaining a high-intensity facility is very challenging
 - Possibility for early repair must exist
 - Consider radiation effects on nearby electronics
 - Intervention on equipment ‘impossible’ after long operation
 - → Remote handling, replacement
 - Ventilation system is a key item
 - Temperature and humidity control
 - Radioactive air management
 - H-3 creation in air and water is an issue
 - Keep redundancy of monitoring
 - Beam-line instrumentation is crucial

Additional Slides

Total Integrated Intensity since CNGS Start 2006

