

---

# Performance and Operational Experience of the CNGS Facility

Edda GSCHWENDTNER, Dario AUTIERO, Karel CORNELIS, Ilias EFTHYMIOPOULOS, Alfredo FERRARI, Alberto GUGLIELMI, Ans PARDONS, Paola SALA Heinz VINCKE, Joerg WENNINGER  
(October 20, 2009)

---

# Outline

- Introduction
- Layout and Main Parameters
- Operational Experience and Performance
- Summary

# CERN Neutrinos to Gran Sasso (CNGS)

long base-line appearance experiment:

- Produce muon neutrino beam at CERN
- Measure tau neutrinos in Gran Sasso, Italy (732km)
  - $\nu_\tau$  interaction in the target produces a  $\tau$  lepton
  - Identification of tau lepton by characteristic kink



2 detectors in Gran Sasso:

- **OPERA**  
(1.2kton) emulsion target detector  
~146000 lead-emulsion bricks
- **ICARUS**  
(600ton) liquid argon TPC

# CNGS: Conventional Neutrino Beams


→ Produce pions and Kaons to make neutrinos



# CERN NEUTRINOS TO GRAN SASSO

## Underground structures at CERN

- █ Excavated
- █ Concreted
- █ Decay tube (2<sup>nd</sup> contract)




# CERN Neutrinos to Gran Sasso

Approved for  $22.5 \cdot 10^{19}$  protons on target  
i.e. 5 years with  $4.5 \cdot 10^{19}$  pot/ year  
(200 days, nominal intensity)

- $2.2 \cdot 10^{17}$  pot/day
- $\sim 10^{17} \nu_{\mu}$  /day
- $\sim 10^{11} \nu_{\mu}$  /day at detector in Gran Sasso
- 3600  $\nu_{\mu}$  interactions/year in OPERA  
(charged current interactions)
- 2-3  $\nu_{\tau}$  interactions detected/year in OPERA

$\sim 1 \nu_{\tau}$  observed interaction with  $2 \cdot 10^{19}$  pot





→ CNGS Run 2008:  $1.78 \cdot 10^{19}$  pot

→ Run 2009 today:  $2.53 \cdot 10^{19}$  pot

# CNGS Proton Beam Parameters

Beam parameters	Nominal CNGS beam
Nominal energy [GeV]	400
Normalized emittance [ $\mu\text{m}$ ]	H=12 V=7
Emittance [ $\mu\text{m}$ ]	H=0.028 V= 0.016
Momentum spread $\Delta p/p$	0.07 % +/- 20%
# extractions per cycle	2 separated by 50 ms
Batch length [ $\mu\text{s}$ ]	10.5
# of bunches per pulse	2100
Intensity per extraction [ $10^{13}$ p]	2.4
Bunch length [ns] ( $4\sigma$ )	2
Bunch spacing [ns]	5
Beta at focus [m]	hor.: 10 ; vert.: 20
Beam sizes at 400 GeV [mm]	0.5 mm
Beam divergence [mrad]	hor.: 0.05; vert.: 0.03

**500kW  
beam power**



**Expected beam performance:  $4.5 \times 10^{19}$  protons/year on target**

# CNGS Challenges

- High Intensity, High Energy Proton Beam (500kW, 400GeV/c)
  - Induced radioactivity
    - In components, shielding, fluids, etc...
  - Intervention on equipment 'impossible'
    - Remote handling by overhead crane
    - Replace broken equipment, no repair
    - Human intervention only after long 'cooling time'
  - Design of equipment: compromise
    - E.g. horn inner conductor: for neutrino yield: thin tube, for reliability: thick tube
- Intense Short Beam Pulses, Small Beam Spot (up to  $3.5 \times 10^{13}$  per 10.5  $\mu$ s extraction, < 1 mm spot)
  - Thermo mechanical shocks by energy deposition (designing target rods, thin windows, etc...)

→ Proton beam: Tuning, Interlocks!

→ most challenging zone: Target Chamber (target–horn–reflector)



---

# CNGS Layout and Main Parameters

## CNGS Primary Beam Line

100m extraction together with LHC, 620m long arc to bend towards Gran Sasso, 120m long focusing section

### Magnet System:

- 73 MBG Dipoles
  - 1.7 T nominal field at 400 GeV/c
- 20 Quadrupole Magnets
  - Nominal gradient 40 T/m
- 12 Corrector Magnets


### Beam Instrumentation:

- 23 Beam Position Monitors (Button Electrode BPMs)
  - recuperated from LEP
  - Last one is strip-line coupler pick-up operated in air
  - mechanically coupled to target
- 8 Beam profile monitors
  - Optical transition radiation monitors: 75  $\mu\text{m}$  carbon or 12  $\mu\text{m}$  titanium screens
- 2 Beam current transformers
- 18 Beam Loss monitors
  - SPS type  $\text{N}_2$  filled ionization chambers

# Primary Beam Line



# CNGS Secondary Beam Line



## Air cooled graphite target

- Target table movable horizontally/vertically for alignment
- Multiplicity detector: TBID, ionization chambers
- 2 horns (horn and reflector)
  - Water cooled, pulsed with 10ms half-sine wave pulse of up to 150/180kA, remote polarity change possible
- Decay pipe:
  - 1000m, diameter 2.45m, 1mbar vacuum, 3mm Ti entrance window, 50mm carbon steel water cooled exit window.
- Hadron absorber:
  - Absorbs 100kW of protons and other hadrons
- 2 muon monitor stations: muon fluxes and profiles

Target magazine: 1 unit used, 4 in-situ spares



# CNGS Target

13 graphite rods, each 10cm long,


$\varnothing = 5\text{mm}$  and/or  $4\text{mm}$

2.7mm interaction length


Ten targets (+1 prototype) have been built. → Assembled in *two* magazines.



# CNGS Horn and Reflector



- 150kA/180kA, pulsed
- 7m long, inner conductor 1.8mm thick
- Designed for  $2 \cdot 10^7$  pulses
- Water cooling to evacuate 26kW
- 1 spare horn (no reflector yet)



## Design features

- Water cooling circuit
  - In situ spare, easy switch
    - $\ll 1\text{mSv}$  total dose after 1y beam, 1w stop
  - Remote water connection
- Remote handling & electrical connections
  - $\ll 1\text{mSv}$  total dose after 1y beam, 1m stop
- Remote and quick polarity change



## Decay Tube

- steel pipe
- 1mbar
- 994m long
- 2.45m diameter,  $t=18\text{mm}$ , surrounded by 50cm concrete
- entrance window: 3mm Ti
- exit window: 50mm carbon steel, water cooled

# CNGS Facility – Layout and Main Parameters

## Muon Monitors

- 2 x 41 fixed monitors (Ionization Chambers)
- 2 x 1 movable monitor

## LHC type Beam Loss Monitors

- Stainless steel cylinder
- Al electrodes, 0.5cm separation
- N<sub>2</sub> gas filling

- Muon Intensity:
  - Up to  $8 \cdot 10^7$  /cm<sup>2</sup>/10.5 $\mu$ s

60cm

270cm


11.25cm

CNGS



# Operational Experience and Performance

# CNGS Timeline



<b>2000-2005</b>	<b>Civil Engineering &amp; Installation</b>	<b>CERN</b>	
<b>2006: 10 July-27 Oct</b>	<b>Beam Commissioning Detector electronics commissioning</b>	<b>CERN Gran Sasso</b>	<b><math>0.08 \cdot 10^{19}</math> pot</b>
<b>2006-2007: Shutdown</b>	<b>Reflector Water Leak Repair/Improvement</b>	<b>CERN</b>	
<b>2007: 17 Sept-20 Oct</b>	<b>Beam Commissioning at high intensity Detector commissioning with 60000 bricks</b>	<b>CERN Gran Sasso</b>	<b><math>0.08 \cdot 10^{19}</math> pot</b>
<b>2007-2008: Shutdown</b>	<b>Additional shielding and electronics re-arrangement Finishing OPERA bricks</b>	<b>CERN Gran Sasso</b>	
<b>2008: 18 June- 3 Nov</b>	<b>CNGS Physics Run</b>		<b><math>1.78 \cdot 10^{19}</math> pot</b>
<b>2009: 1 June-today</b>	<b>CNGS Physics Run</b>		<b><math>2.4 \cdot 10^{19}</math> pot</b>

# CNGS Performance

## 2008: 18 June – 3 November 2008

- Excellent performance of the CNGS Facility
- CNGS modifications finished successfully
- Beam line equipment working well and stable

→  $1.78 \cdot 10^{19}$  protons on target

→ OPERA experiment:

- 10100 on-time events
- 1700 candidate interaction in bricks


## 2009: 28 May – 23 November 2009

→ 16<sup>nd</sup> October 2009:  $2.53 \cdot 10^{19}$  protons on target


→ OPERA experiment:

- >15500 on-time events
- >2500 candidate interaction in bricks

# Supercycle 2008




48s supercycle:  
 North Area, 3 CNGS, 1LHC,1MD  
 → 37.5% CNGS duty cycle




50.4s supercycle: 7 CNGS, 1 LHC  
 → 83% CNGS duty cycle

# Supercycle 2009

46.8s supercycle:  
 North Area, 4 CNGS, 1LHC  
 → 51.3% CNGS duty cycle




# CNGS Run 2008: 18 June- 03 Nov 2008





# 2009 Protons on Target


Total POT expected 2009: 3.22E19



# SPS Efficiencies for CNGS




# Total Protons on Target







# Primary Beam

- Extraction interlock in LSS4 modified to accommodate the simultaneous operation of LHC and CNGS
  - Good performance, no incidents
- No extraction and transfer line losses
- Trajectory tolerance: 4mm, last monitors to +/-2mm and +/- 0.5mm (last 2 monitors)
  - Largest excursion just exceed 2mm
- Total trajectory drift over 2008 is ~1mm rms in each plane



# Target Beam Position

- Excellent position stability;  $\sim 50$  ( $100$ )  $\mu\text{m}$  horiz(ver) over entire run.
- No active position feedback is necessary
  - 1-2 small steerings/week only



Horizontal and vertical beam position on the last BPM in front of the target

# On-line Muon Profiles



CNGS.TNM/Acquisition

ser: SPS.USER.CNGS1 Time: 26.06.2008 14:53:14



BFCT  
 Extraction 1: 9.1301E12  
 Extraction 2: 9.3050E12

Movable Monitor Pit 1  
 Extraction 1: 3.3615E-01  
 Extraction 2: 3.3662E-01

Movable Monitor Pit 2  
 Extraction 1: 1.1106E-02  
 Extraction 2: 1.1088E-02




Centroid for each profile and extraction



# Beam Stability seen on Muon Monitors

- Position stability of muon beam in pit 2 is  $\sim 2$ cm rms
- Beam position correlated to beam position on target.
  - Parallel displacement of primary beam on T40


Moun Beam Position



# Muon Monitors

Very sensitive to any beam changes !

- Offset of beam vs target at 0.05mm level  Muon Profiles Pit 2



- Offset of target vs horn at 0.1mm level


- Target table motorized
- Horn and reflector tables not



Muon Profiles Pit 1


# Beam Intensity

T40 Intensity





Typical transmission of the CNGS beam through the SPS cycle  $\sim 92\%$ . Injection losses  $\sim 6\%$ .

BFCT.TT41



# Muon Detector Non-Linearity Puzzle

2007: observation: non-linear muon detector signal in horizontal profile of pit 1  
(not in vertical profile, neither in profiles of pit 2)



Looks like saturation effect  
But:

Check:

Timing?  
Electronics cards?  
Beam intensity?

...

A. Marsili et al, AB-2008-044-BI


# Muon Detector Non-Linearity Puzzle

## Wire topology:

All detectors are connected to readout card via a 750m long twisted multi-wire cable.

→ Horizontal profile detectors are inside the multi-wire cable

→ See different capacitances!




## Remedy:

Increase capacitance of all wires to a fixed value:

→ adding 220nF capacitor between each wire and shielding.


Cross 41, H

2009





# CNGS Polarity Puzzle




Sensitive to any beam change (e.g. offset of beam vs target at  $50\mu\text{m}$  level)

→ Online feedback on quality of neutrino beam

Observation of asymmetry in horizontal direction between


- Neutrino (focusing of mesons with positive charge)
- Anti-neutrino (focusing of mesons with negative charge)



# CNGS Polarity Puzzle


Explanation: Earth magnetic field in 1km long decay tube!

- calculate B components in CNGS reference system
- Partially shielding of magnetic field due to decay tube steel
- Results in shifts of the observed magnitude
- Measurements and simulations agree very well (absolute comparison within 5% in first muon pit)




# Muon Monitors: Measurements vs. Simulations


Horizontal Profile Pit 1




Horizontal Profile Pit 2



Vertical Profile Pit 1



Vertical Profile Pit 2



● Measurements  
◆ Simulations

→ Excellent agreement!

P. Sala et al, FLUKA simulations 2008

# Summary

- CNGS commissioned in 2006
- Successful modifications in the CNGS facility and completion of the OPERA Detector
- Physics run since 2008
  - 2008:
    - $1.78 \cdot 10^{19}$  protons on target total
  - 2009:
    - Expect  $3.2 \cdot 10^{19}$  protons on target total
    - Today (16 October 2009):  $2.53 \cdot 10^{19}$  protons on target

**→ Waiting for tau neutrino results!!**

- Additional Slides



# CNGS Performance - Reminder

## Examples: effect on $V_{\tau}$ cc events


horn off axis by 6mm	< 3%
reflector off axis by 30mm	< 3%
proton beam on target off axis by 1mm	< 3%
CNGS facility misaligned by 0.5mrad (beam 360m off)	< 3%

---

# Helium Tube Entrance Window




- 0.3mm thick
- 0.8m inner diameter
- Clamped with seal between flanges



Titanium Grade (Ti-6Al-4V)

- Ultimate stress:
  - @20°C: >900MPa
  - @100°C: >870MPa
  - @150°C: >850MPa



## From calculations:

- When ventilation vs. beam is such that temp. at flange = 66°C:
  - Window: Temp. <100°C & Stress <250MPa → **Safety factor 3 ensured.**


## From temperature measurements during operation (extrapolate):

- If temp. measured < 85°C
  - Window: Temp. <150°C & Stress <300MPa → **Safety factor 2.5 ensured.**

Courtesy of A. Pardons

FermiLab, 20 October 2009

# Helium Tube Entrance Window Temperature






# CNGS Radiation Issues

CNGS: no surface building above CNGS target area

→ many electronics in tunnel area

- During CNGS run 2007:
  - Failure in ventilation system installed in the CNGS tunnel area due to radiation effects in electronics (SEU due to high energy hadron fluence).
- modifications during shutdown 2007/08:
  - Move most of the electronics out of CNGS tunnel area
  - Create radiation safe area for electronics which needs to stay in CNGS
  - Add shielding → 53m<sup>3</sup> concrete → up to 6m<sup>3</sup> thick shielding walls



# Neutrino Parameter Status: July 2008 Review of Particle Physics

If flavor eigenstates and mass eigenstates are different (mixing) and if masses are different  
 → neutrino oscillation

$$\begin{array}{l} \text{Mass states: } |\nu_1\rangle \quad |\nu_2\rangle \quad |\nu_3\rangle \\ m_1, m_2, m_3 \quad \Delta m_{12} = m_2 - m_1, \quad \Delta m_{23} = m_3 - m_2 \end{array} \quad \begin{array}{l} \text{Flavor states: } |\nu_e\rangle \quad |\nu_\mu\rangle \quad |\nu_\tau\rangle \end{array}$$

Mixing of the three neutrinos: unitary 3x3 matrix → 4 parameters like the CKM matrix for Quarks.  
 CP violating phase not yet accessible → currently 3 mixing angles  $\theta$ .

$$|\nu_\alpha\rangle = \sum_{n=1}^3 U_{\alpha n}^* |\nu_n\rangle \quad \sim \quad \begin{pmatrix} |\nu_\mu\rangle \\ |\nu_\tau\rangle \end{pmatrix} = \begin{pmatrix} \cos \theta_{23} & \sin \theta_{23} \\ -\sin \theta_{23} & \cos \theta_{23} \end{pmatrix} \begin{pmatrix} |\nu_2\rangle \\ |\nu_3\rangle \end{pmatrix}$$

$$P_{\mu \rightarrow \tau} = \sin^2(2\theta_{23}) \sin^2\left(\frac{\Delta m_{23}^2 L}{4E}\right)$$

$$\Delta m_{21}^2 = 8 \pm 0.3 \times 10^{-5} \text{ eV}^2$$

$$\Delta m_{21} = 9 \pm 0.17 \text{ meV}$$

solar and reactor Neutrinos

$$\Delta m_{32}^2 = 2.5 \pm 0.5 \times 10^{-3} \text{ eV}^2$$

$$\Delta m_{32} = 50 \pm 5 \text{ meV}$$

Atmospheric and long Baseline

$\sin^2 2\theta_{23} > 0.93$  →  $\theta_{23} = 35.3$  degrees compatible with max. mixing  $\theta = 45$  degrees

# Neutrinos

Weakly interacting leptons  $\nu_e$ ,  $\nu_\mu$ ,  $\nu_\tau$ , no charge

- Solar Neutrinos:
  - $6 \cdot 10^{14}$  neutrinos/s/m<sup>2</sup>
    - Every 100 years 1 neutrino interacts in human body
    - $10^{16}$  meter lead to stop half of these neutrinos
- Natural radioactivity from earth:
  - $6 \cdot 10^6$  neutrinos/s/cm<sup>2</sup>.
- <sup>40</sup>K in our body:
  - $3.4 \cdot 10^8$  neutrinos/day
- Cosmic neutrinos:
  - 330 neutrinos/cm<sup>3</sup>
- **CNGS**
  - Send  $\sim 10^{17}$  neutrinos/day to Gran Sasso

# Neutrino Introduction

→  $\Delta m_{32}^2 \dots$  governs the  $\nu_\mu$  to  $\nu_\tau$  oscillation

$$P_{\mu \rightarrow \tau} = \sin^2(2\theta_{23}) \sin^2\left(\frac{\Delta m_{23}^2 L}{4E}\right)$$

→ Up to now: only measured by **disappearance of muon neutrinos**:

- Produce muon neutrino beam, measure muon neutrino flux at near detector
- Extrapolate muon neutrino flux to a far detector
- Measure muon neutrino flux at far detector
- Difference is interpreted as oscillation from muon neutrinos to undetected tau neutrinos

→ K2K, NuMI

→ **CNGS (CERN Neutrinos to Gran Sasso):**

long base-line **appearance experiment**:

- Produce muon neutrino beam at CERN
  - Measure tau neutrinos in Gran Sasso, Italy (732km)
- Very convincing verification of the neutrino oscillation

→  $\nu_\tau$  interaction in the target produces a  $\tau$  lepton

→ Identification of tau lepton by characteristic kink

**2 detectors in Gran Sasso:**

- **OPERA** (1.2kton) emulsion target detector  
~146000 lead-emulsion bricks
- **ICARUS** (600ton) liquid argon TPC

