



CERN infrastructure

A.Fabich, CERN AB-ATB

All information available at
<http://cern.ch/proj-hiptarget>




Experimental requirements

What CERN could provide?

- Primarily a technical review
- Cost/ estimates exist, but no official CERN management confirmation of availability and support
- ▶ Space
- ▶ Beam
- ▶ Support on
 - installation
 - Cryogenics
 - solenoid power
 - Safety

CERN accelerator chain


- ▶ TT2 – transfer tunnel from Proton Synchrotron to AD, SPS
- ▶ TT2A – PS transfer line to nToF




LHC: Large Hadron Collider
 SPS: Super Proton Synchrotron
 AD: Antiproton Decelerator
 ISOLDE: Isotope Separator OnLine DEvice
 PSB: Proton Synchrotron Booster
 PS: Proton Synchrotron
 LINAC: LINear ACcelerator
 LEIR: Low Energy Ion Ring
 CNGS: Cern Neutrinos to Gran Sasso

Radolf LEIR, PS Division, CERN, 02.09.96
 Revised and adapted by Antonella Dal Ross, ETT Div.,
 in collaboration with R. Desforges, SL Div., and
 D. Manglani, PS Div. CERN, 23.05.01

TT2Δ



nToF




16.Feb.2005

MC meeting, LBNL

from PS


Access & transport

- ▶ Access to TT2A during PS operation towards SPS possible




- ▶ Pedestrian access via TT2
- ▶ Material access shaft in TT2
- ▶ Tight turn from TT2 to TT2A

Cryogenics



- ▶ Dewar at surface
- ▶ Supply and exhaust via 60 m long piping
- ▶ Reuse of existing equipment
- ▶ Details in RAL contribution




Access route for LN2 delivery

16.Feb.2005

MC meeting

Power supply for solenoid

1. Type Alice/LHCb



New - Used by LHC exp.

2. West Area power supply




From dismantling West Area -
Refurbishment needed

Power supply for solenoid

	Alice/LHCb	WA PS	required
Voltage [V]	< 900	< 1000	740
Current [A]	< 7200	< 8000	7200
costs	~300 kChF	~ 100 kChF	~ 0 kChF

- ▶ Further use in US or Japan considered




Power net:

- ▶ 18 kV cells in building 193
- ▶ Cable installation ~70 kChF
- ▶ Currently investigating impact on power net (spikes)


PS beam

- ▶ Momentum: $< 24 \text{ GeV}/c$
- ▶ 8 buckets to fill ($h=8$)
 - $T = 2 \mu\text{s}$
 - spacing: 250 ns
- ▶ 4 bunches (within one sub-cycle)
 - $l = 13 \text{ ns r.m.s.}$
 - to our discretion in the 8 buckets
 - Multi-bunch single turn extraction
- ▶ Pulse length: $0.25 - 2 \mu\text{s}$
- ▶ Intensity:
 - $< 0.7 \cdot 10^{13}$ protons/bunch
 - Total $< 3 \cdot 10^{13}$ p.o.t./extraction



Beam at experiment

- ▶ Beam horizontal
 - According to geometer: $\Delta h=5\text{mm}$ over 100m
 - Beam height: 121 cm above ground
- ▶ Floor horizontal
- ▶ Spot:
 - $r < 2 \text{ mm}$





Safety



- ▶ Radiation
- ▶ Mechanical safety
- ▶ Mercury
- ▶ LN2 cooling
- ▶ High magnetic field
- ▶ ...
- ▶ "Waste" management

Procedure established:

- ▶ Define requirements/specs
- ▶ Prepare layout/design
- ▶ Safety review

SAFETY CONTACT PERSON FOR ALL MATTERS:

Herve Buret Tel.: 160013 (replacement since Oct.2004, former Bruno PICHLER tel: 16 0889 or 73362)

	Responsible
DSO of AB	Paolo CENNINI
General Safety	Bruno PICHLER
Radiation	Thomas OTTO
Gas and Chemicals	Jonathan GULLEY
Electricity	Fritz SZONCSO
Emergency stops	
Magnetic Field	
Laser	
Fire	Fabio CORSANEGO (material also J.Gulley)
Material	
Mechanical safety	Alberto DESIRELLI
-----	also Maurizio BONA
Cryogenics	Gunnar LINDELL

Memos available

Radio-Protection

- ▶ Activation
 - Beam line
 - Mercury
- ▶ High intensity proton beam towards nToF target
 - beam attenuator
- ▶ Access
 - protected by
 - ▶ Two beam stoppers
 - ▶ Upgraded shielding during shutdown 2003/2004
 - ▶ Radiation monitor in TT2A

Safety

Mercury loop

- Construction at ORNL
- 6 to 8 Liter mercury
- Experience
 - at ORNL and CERN
- Double containment
- ISO 2919 "sealed sources"

Radiation

- ALARA
- Minimum number of integrated protons
 - < 3 10¹⁵ (~100 pulses)**
- Activation of area and mercury

Chemicals

- Minimum amount of mercury
- Continuous vapor monitoring
 - Inside secondary containment
- Define procedures/operation

Safety

Mechanical safety

- ▶ According to CODAP2000/ASME
- ▶ Double containment
- ▶ Pressure vessel

Cryogenics

- ▶ Standards used
- ▶ ODH study

- ▶ **Beam attenuator**
 - to protect nToF target
- ▶ controls, interlocks

- ▶ decommissioning
- ▶ Waste management

Decommissioning

- ▶ removal of all equipment
 - Approx. 2 weeks to restore beam line
- ▶ **“Waste” management**
 - Activated mercury returned to ORNL
 - Solenoid shipped to Japan
 - Power supply considered for further use
 - Mercury loop goes with solenoid
 - ... reused in Japan/US?

Summary

- ▶ Integration of experiment technically possible!
 - No safety obstacles
- ▶ DG approval needed ...