

Hg System Status

V.B. Graves


P.T. Spampinato

Muon Collaboration Friday Meeting

October 20, 2006


Initial Water Testing Setup

- A primary containment has been mocked up to allow initial water tests to be performed
- Will be used to debug Labview control software and test some of the sensors
- Remainder of syringe hardware scheduled for delivery week of Oct 23



Control System Connections

- Most internal Labview wiring completed
- Temporary wiring for sensors required for testing
- Remainder to be completed upon delivery of wiring pkg from Princeton




Current wiring



At last review

Syringe Pump Performance Testing

- **Control system development complete based on water tests**
 - Minor modifications may be required after switch to Hg, but none are expected
 - Data logging incorporated
- **System can produce a 20m/s, 1cm-dia water jet**
 - Water test nozzle configuration approximately matches one of the two Hg nozzles
 - *My opinion: jet quality looks good for a no-field condition. Holds together for better than ~1/2m*



Water Test 20m/s Screenshot



OAK RIDGE NATIONAL LABORATORY
U. S. DEPARTMENT OF ENERGY


Load Testing of Common Baseplate & Target Cart



- **CERN Safety Commission voiced concerns regarding analysis performed on common baseplate design**
- **Load test performed on structures to verify strength and test adjusting mechanisms**
- **Estimated component weights**
 - Magnet: 12000 lbs (5440 kg)
 - Hg system (with 23liters Hg): 4000 lbs (1810 kg)
- **Test weights**
 - Magnet: 13600 lbs (6170 kg) = 113% estimated weight
 - Hg system: 4500 lbs (2040 kg) = 113% estimated weight

In Nominal Test Position

- Baseplate tilt $\sim 66\text{mrad}$
- Elevation matches CAD models



OAK RIDGE NATIONAL LABORATORY
U. S. DEPARTMENT OF ENERGY

Operational Testing

- Lifting jacks and lateral position adjustment mechanisms tested



OAK RIDGE NATIONAL LABORATORY
U. S. DEPARTMENT OF ENERGY

Roller Testing

- Loaded baseplate pushed with pallet jack while on three Hilman rollers



OAK RIDGE NATIONAL LABORATORY
U. S. DEPARTMENT OF ENERGY

Leveling Jack Testing

- Baseplate adequately supported by four leveling jacks



OAK RIDGE NATIONAL LABORATORY
U. S. DEPARTMENT OF ENERGY



Conclusions

- **Syringe pump control system development completed**
- **System can produce 20m/s water jet within pump's performance limits**
 - No reason to think Hg will be different
- **MERIT common baseplate has been successfully tested with 113% expected loading**
- **Final assembly and optics integration to commence shortly**
- **Switch to Hg will be made once all operational aspects of system have been tested with water**



Conclusions

- **Manual control of syringe demonstrated**
- **Hydraulic system fill and drain procedures developed**
- **Hg control system wiring is underway, water tests to start afterwards**
- **Ready for Hg testing after conclusion of water tests and when remainder of fabricated components available**