

Hg System Status

V.B. Graves


P.T. Spampinato

Muon Collaboration Friday Meeting

Aug 4, 2006


Syringe Pump at ORNL

- **Hydraulic power unit (HPU) and syringe cylinders delivered to ORNL July 21**
 - Hg cylinder discharge piping shipped separately due to weld inspection problems, delivered Aug 1
- **Cylinders set directly on target cart until secondary containment received**



HPU Setup

- Hydraulic fluid fill and drain process developed using peristaltic pump
 - Pump works well, takes ~30 min to fill system
- Fluid filter assembly added to HPU




Manual Control Operational

- Fluid added to HPU and hoses connected to syringe cylinders
- Manual control on HPU used to stroke cylinders




Initial Water Testing Setup

- A primary containment has been mocked up to allow initial water tests to be performed
- Will be used to debug Labview control software and test some of the sensors



Control System Connections

- **Calibrated position sensors**
- **Labview hardware installed in HPU cabinet**
- **Wiring to start later this week**
- **Initial version of Labview software complete, ready for test and debug once wiring in place**



Other Fabrications

- **Secondary containment progressing at Princeton**
- **Jet chamber shell weldment completed, machining to proceed soon**



OAK RIDGE NATIONAL LABORATORY
U. S. DEPARTMENT OF ENERGY



Conclusions

- **Manual control of syringe demonstrated**
- **Hydraulic system fill and drain procedures developed**
- **Hg control system wiring is underway, water tests to start afterwards**
- **Ready for Hg testing after conclusion of water tests and when remainder of fabricated components available**