

# MERIT Hg System Testing Status

**V.B.** Graves

P.T. Spampinato

Neutrino Factory Muon Collider Collaboration Meeting
UCLA
Jan 29, 2007

OAK RIDGE NATIONAL LABORATORY U. S. DEPARTMENT OF ENERGY

#### Outline



- Requirements review
- System description
- Testing to date
- Preparations for CERN
- Next steps

# Requirements and Operating Conditions





#### Target system must deliver a stable, unconstrained jet of Hg into a 15 Tesla field

- 1-cm diameter jet at 20 m/s delivered every 30 minutes
  - Q=1.6liter/s
- Steady state jet must exceed magnet peak field duration
- Hg environment is 1-atm air
- Two barriers between Hg and tunnel environment
- Small angles between magnet axis, jet, and beam
- Up to 100 pulses for the CERN test

# MERIT Side View







# Hg Delivery System



- Syringe pump
- Hydraulic power unit w/control system
- Optical diagnostic system
- Baseplate support structures



#### Syringe Pump System

- Primary containment
  - Hg-wetted components
  - Capacity 23liters Hg (~760 lbs)
  - Jet duration up to 12 sec
- Secondary containment
  - Hg leak/vapor containment
  - Ports for instruments, Hg fill/drain, hydraulics
- Optical diagnostic components
  - Passive optics
  - Shadow photography
- Beam Windows
  - Ti alloy components that directly interact with beam
  - Single windows on primary, double windows on secondary




## Syringe Statistics

- 30hp / 4000psi / 12.9gpm hydraulic pump
- 40 gal vegetable-oil based hydraulic fluid
- Hg flow rate 1.6liter/s (24.9gpm)
- Piston velocity 3.0cm/s (1.2in/sec)
- Up to 100 bar (1500 psi)
   Hg pressure in cylinder
- Hg cylinder force 525kN (118kip)



# LabView-Based Control System

- Control room will be housed in remote location from experiment, requiring network control of equipment
- LabView on laptop computer was chosen as system controller
  - CompactFieldPoint sensor modules housed in HPU control cabinet



## Instrumentation & Sensors


Controlled Components			
Hydraulic pump	Proportional control valve		
Analog Sensor Inputs			
Hg discharge pressure	Hg level	Hg vapor 1	Hg vapor 2
Cylinder 1 position	Cylinder 2 position	Beam window 1 pressure	Beam window 2 pressure
Hydraulic fluid port pressures	Eight RTDs		
Digital Sensor Inputs			
Hydraulic filter dirty switch	Hydraulic low level switch	Hydraulic fluid high temperature	Conductivity probe leak detector
Beam trigger			

#### SS Water Test Nozzles

Muon Collider

Nozzle B

- Nozzle A diameter reduction after bend, 2.5° nozzle angle
- Nozzle B reduction before bend, 2.5° nozzle angle
- Nozzle C test nozzle with reduction after bend, straight nozzle tip, internally similar to nozzle A
- Nozzle D nozzle A after reaming out the tip






#### Results

- Nozzle B spray worse than Nozzle A
  - Neither jet was acceptable
- Definite increase in jet diameter at higher velocities
- Nozzle C gave best results
- Water droplets on windows was a problem




Nozzle A, 20m/s



Nozzle C, 20m/s






Nozzle B, 20m/s

#### Nozzle Issues



- Flow path is a three-piece weldment
  - Inlet tube
  - Nozzle flange
  - Short angled nozzle tip
- Change in direction required for beam to miss piping geometry
- Smooth path requires constant ID
- Investigation revealed SS nozzles had step in flow path (flange thru hole smaller than tube IDs)



Dimensions in inches


#### Nozzle D Tested



- Nozzle A was manually modified using drill bits to provide nearly constant ID from flange to tip
- Tests showed definite improvement, but still not satisfactory
  - Field of view 5.5cm, so Nozzle D generates ~2cm jet



Nozzle A, 20m/s




Nozzle D, 20m/s

# Nozzle E configuration



- Straight flow path after 180deg bend
- "Kink" made prior to bend
- Fabricated from final Ti materials



#### Ti Nozzle Fabrication


- Final nozzle configuration fabricated from grade 2 and grade 5 Ti
- Assembly anodized after welding
- Fabrication error in assembly length
  - Requires removal of 1" piping





#### Ti Nozzle Testing


- Nozzle testing compromised due to installation issues
  - Most interested in jet shape in these tests
  - Could not install nozzle in final position, so jet direction and angle measurements not meaningful





#### Visual Results

- Visual observation noted jet shape much improved over previous nozzle configurations
  - Observations verified by optical diagnostics system
- Any directional issues will be resolved once final assembly takes place



#### Nozzle Modification Status




- Initial water testing of Ti nozzle completed Jan 25
- Nozzle assembly taken to local Oak Ridge fabricator for modification
  - Cutting, re-welding, x-ray weld inspection, assembly pressure testing
- Modified assembly due back Jan 30
- Installation and additional testing will start Jan 31
- If no further problems encountered, Hg testing will commence a few days later

#### Other Activities

- Handling/lifting tests
- Hg vapor monitor testing at 10m tubing lengths
- Baseplate tests
- Assembly tests





# Shipping

- Shipping issues have required more resources & attention than expected
- Custom crates for Hg system, HPU, & magnet procured
  - Certified for international shipment (ISPM-15)
- 12 flasks Hg on their way to CERN
  - Separate Hg supply will be used at MIT



## Next Steps



- Install modified Ti nozzle
- Conclude water tests
- Drain system, clean viewports, load Hg
- Conduct Hg tests and drain system
- Pack and transport to MIT for integrated testing in February
- Air-ship entire system to CERN in March

#### **Final Comments**



- Syringe pump system functions as designed (at least with water!)
- Optical diagnostics integrated with Hg system & is operational
- Safety & monitoring equipment tested
- Transportation plan developed and in place

