


J-PARC High Intensity Neutrino Beam

**T. Sekiguchi (KEK)
on behalf of T2K Beam Group**

Contents


- **Introduction to J-PARC Neutrino Beamline**
- **Current Status**
- **Prospect for Beamline Upgrade**

J-PARC



J-PARC

J-PARC is a versatile experimental facilities for various fields of science




Linac
(330m)

Rapid Cycle Synchrotron (RCS)
(3 GeV synchrotron)
(25 Hz, 1MW)

Main Ring (MR)
(30 GeV synchrotron)
(0.75MW)

Neutrino Experimental Facility

J-PARC Neutrino Beamline





Features of J-PARC Neutrino Beamline

- **High intensity beam**

- **750 kW** proton beam (30 GeV, 3.3×10^{14} protons/pulse)

- **Off-axis neutrino beam (2~2.5°)**


- **Narrow band beam** ~ 0.6 GeV
 - flux peak at 1st oscillation max.



Design Philosophy of Neutrino Beamline

- **Tolerance for high power beam**
 - All beamline components designed for 750 kW beam
 - Equipments that cannot be replaceable after irradiation are designed for 3 or 4 MW beam.
- **Remote maintenance**
 - Secondary beamline equipments are highly irradiated with more than 1 Sv/h.
 - Beamline components inside Target Station can be replaceable remotely.

Secondary Beamline



- Target Station (includes target and horns)
- Decay Volume
- Beam Dump

Target Station




Horn1

26mm ϕ x 910mm
Graphite
IG-430U

Ti-6Al-4V
(0.3mmT)
He-gas cooling

Target



All equipments inside Helium Vessel can be replaceable

Target

Graphite target





- 26mm ϕ \times 910mm-long rod (IG-430U)
- Covered by 0.3mm-thick Ti case

Helium cooling

- Cooled with 200m/s helium flow
- Thermal stress @ $\Delta T \sim 200\text{K} \Rightarrow \sim 7\text{ MPa}$
 - Tensile strength 37 MPa
 - Radiation damage is key issue

Remote exchange

- Exchangeable with manipulators



Magnetic Horn

- **Aluminum alloy conductors (A6061-T6)**


- Coaxial cylindrical structure
 - inner= $t3\text{mm}$, outer= $t10\text{mm}$
- Allowable stress= 25 MPa (taking into account corrosion)
 - Safety factor ~ 2

- **320 kA pulsed current (rated)**

- 2.1 T (max.) toroidal field
- 2~3 ms pulse width
- 2.48 s cycle \Rightarrow **1.3 s for 750 kW**

- **Water cooled**

- Total heat load 25 kJ @ 750 kW
 - 15 kJ (beam) + 10 kJ (Joule)
- Spraying water to inner conductor



Target Station / Decay Volume / Beam Dump

Decay Volume (DV)

- 100 m long
- 2~2.5° OA angle for SK and HK
- water-cooled iron \Rightarrow 4 MW beam acceptable

Beam Dump (BD)


- Graphite core + water-cooled Al plates
- Acceptable for 3 MW beam

Helium Vessel (TS, DV, BD)

- 1500 m³ gigantic helium vessel
 - Filled with 1 atm. helium gas.

Helium Vessel @ TS



Maximum 77 MPa




Decay Volume



Beam Dump



Operation Status



- **Achieved beam power so far**
 - **335~350 kW** continuous operation
 - **1.8×10^{14} protons/pulse** \Rightarrow world's highest intensity
- **Accumulated 1.1×10^{21} POT**
 - 7.0×10^{20} POT for neutrino mode
 - 4.0×10^{20} POT for anti-neutrino mode

Limitation for High Power Beam

- **What are real problems in high power operation?**
 - Things to be well considered at design stage.
 - Mechanical strength
 - Cooling
 - Fatigue
 - These issues are major consideration, however,
- **In reality, beam power is limited by**
 - **treatment of radioactive wastes**
 - radioactive water.
 - radioactive air.
 - **production of hydrogen from water radiolysis**

Radio-active Water Disposal

- **Radio-active water @ 750 kW**

- ${}^7\text{Be}$: 300 GBq/year \Rightarrow 99.9% removed by Ion Exchangers.

- ${}^3\text{T}$: 150 GBq/year \Rightarrow Diluted many times (80 times/year)


- **Limited dilution tank size \rightarrow 0.5 MW**

- Highly-activated water can be taken by **tanker truck**.

- 750 kW will be accepted.

- For BD/DV downstream cooling water, connection equipment for tanker truck was prepared and tested.

Water disposal system at TS



Hydrogen Production in Horns

- **H₂ produced by water radiolysis**

- Expected production rate $\sim 40\text{L/day@750kW}$



- **Hydrogen removal by recombination**

- **Forced flashing inside horns** \Rightarrow H₂ reaches catalyst efficiently

- H₂ density after 2 week operation $< 0.7\%$ @335 kW

- **1 MW beam acceptable** (w/ keeping H₂ density $< 2\%$)

- Degasifier will be introduced for higher recombination efficiency.



Current Acceptable Beam Power

Component	Limiting factor	Acceptable value
Target	Thermal shock	3.3×10^{14} ppp
	Cooling capacity	0.75 MW
Horn	Conductor cooling	2 MW
	Stripline cooling	0.54 MW
	Hydrogen production	1 MW
	Operation	2.48 sec. & 250 kA
He Vessel	Thermal stress	4 MW
	Cooling capacity	0.75 MW
Decay Volume	Thermal stress	4 MW
	Cooling capacity	0.75 MW
Beam Dump	Thermal stress	3 MW
	Cooling capacity	0.75 MW
Radiation	Radioactive air disposal	1 MW
	Radioactive water	0.5 MW

10 Year Term Plan of Beam Power Improvement

- **Design beam power = 750 kW**
 - Will be achieved in 2018
 - Beam power over 750 kW is recently being considered.
- **Aim for 1.3 MW beam by 2026**
 - Proton intensity = **3.2×10^{14} protons/pulse.**
 - Repetition cycle = **1.16 sec.** with new MR power supplies.
- **Can our beamline accommodate to 1.3 MW beam?**

Beam Power	# of protons/pulse	Rep. rate
350 kW (achieved)	1.8×10^{14}	2.48 sec.
750 kW (proposed) [original plan]	2.0×10^{14} [3.3×10^{14}]	1.30 sec. [2.10 sec.]
1.3 MW (proposed)	3.2×10^{14}	1.16 sec.

Prospect for Hardware Upgrade

- **Cooling capacity**
 - Apparatuses themselves can withstand 1.3 MW beam.
 - **Improvement of flow rate both for water and helium circulations is needed.**
 - Replacement with larger pumps
 - Replacement with larger-size plumbing
 - \Rightarrow These will be feasible but need 1 year for modification.
- **Radiation**
 - **Radioactive air**
 - Reinforcement of air-tightness \Rightarrow 1.3 MW can be manageable.
 - **Radioactive water disposal**
 - Enlargement of dilution tank
 - Modification of existing tank \Rightarrow ~1.3MW
 - New facility building for water disposal \Rightarrow 2MW
 - 2 years for construction (no beam stop needed)

Horn Operation Improvement

Operation status


- **250 kA** operation for physics data taking since 2010.
 - Mainly due to refurbishment of old K2K PS (rated 250 kA).
- Currently, operated with **2.48 s cycle**.
 - 1.3 s for 750 kW (not operated with the existing PS)

3 PS configuration for 320 kA and 1 Hz operation

- New power supply developed (2 PS's already produced).
- Also, low impedance striplines newly developed.

Timeline

- Production of the last PS, transformers, part of striplines
- Aim to start 320 kA operation from summer 2017.



Improved Acceptable Beam Power

Component	Limiting factor	Acceptable value
Target	Thermal shock	3.3×10^{14} ppp
	Cooling capacity	>1.5 MW
Horn	Conductor cooling	2 MW
	Stripline cooling	1.25 MW
	Hydrogen production	>1 MW
	Operation	1 sec. & 320 kA
He Vessel	Thermal stress	4 MW
	Cooling capacity	>1.5 MW
Decay Volume	Thermal stress	4 MW
	Cooling capacity	>1.5 MW
Beam Dump	Thermal stress	3 MW
	Cooling capacity	>1.5 MW
Radiation	Radioactive air disposal	>1 MW
	Radioactive water	0.75 → 1.3 or 2 MW

Summary

- **J-PARC Neutrino Beamline**
 - High intense narrow band beam.
 - Designed for 750 kW beam
- **Operation status**
 - 350 kW stable operation so far.
 - Need improvements on some components such as radiation issues, hydrogen production and so on.
- **Beamline improvement**
 - 1.3 MW beam scenario is being discussed.
 - Necessary improvements
 - Higher cooling capacity for every components
 - Treatment of radioactive wastes
 - Horn operation (320 kA and 1 Hz)

Supplemental Slides

Stripline Cooling

- **Forced helium flow for stripline cooling.**

- Large heat deposit at Horn2 (due to defocused pions)
- Insufficient helium flow rate for Horn2. → 0.54 MW
- **Double flow rate for Horn2 → 1.25 MW**

- **Water-cooled striplines**

- Necessary when beam power goes beyond 1 MW.
- Under conceptual design.

	Horn1	Horn2	Horn3
Heat flux per stripline plate (J/m ²) @ 1.3 MW			
Total (Beam + Joule)	214	1066	141
Acceptable Beam Power			
w/ current flow rate	2.10	0.54	3.46
w/ double flow rate	-	1.25	-

Radio-active Water Disposal

- **For beam power > 750 kW,**


- larger dilution tanks are necessary.

- **Solutions**

- Enlarging the existing dilution tank \Rightarrow 1.3 MW at max.


- **New facility building** for radio-active water disposal \Rightarrow **2 MW**

- Its operation can be started from 2018 in earliest case.




Radioactive Air

Chimney stack



Radioactive Air




Improvement of Air Tightness

Caulking between concrete shields




Lay the air-tight sheet




**Air-tight sheet
(made of the same material for balloon)**

**Protection sheet
(over air-tight sheet)**




Lay the protection sheet under air-tight sheet

Radioactive Air (Current)




Radioactive Air (Improvement Plan)



Flux Improvement by Neutrino Beamline

- **Magnetic horn current**

- 250 kA \Rightarrow 320 kA (rated)
- **10 % improvement of neutrino flux at far detector**




Courtesy of T.Nakadaira

Flux Improvement by Neutrino Beamline

- Another benefit of 320 kA operation
 - Low contamination of wrong-sign neutrino background
 - 5~10% reduction at peak ($E_\nu \sim 0.6$ GeV)

Neutrino mode



Anti-neutrino mode

